Abstract estimate for Restoring Kurubarahalli Tippasunte Register No. 623—819, Kolar Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
					Rs.
1	Earthwork to bund with watering and tamping with lead and lift, etc., complete.	C.yd.	Rs.	4,780	
2	Tusfing.	Sq.yd.		3,759	
3	Removing and resetting old stone work with new jelly.	C.yd.		188	
4	New stone work with jelly	,,		557	
5	Providing and fixing new grade stone with numbering painting.	Each		16	
6	Do do do ..	,,		16	
7	Do gauge stones	,,		1	
8	Do Registered No. stones ...	,,		1	
9	Bench mark stones	,,		2	
10	Cutting jungle and removing ant hills	Lump	sum		
	Total Bund ...	..	..	...	..
	Sluice.				
1	Earthwork excavation	C.yd.		39	
2	Refilling the same with watering and tamping ...	,,		39	
3	Surki concrete	C.ft.		335	
4	Burnt brick in surki mortar	,,		161	
5	Burnt stone slabs 4" to 6"	Sq.ft.		159	
6	Plastering with surki mortar	,,		3·96	
7	Providing wooden and plug and rod with locking arrangements.	Lump	sum		
8	Cutting holes in cross and orifice slabs	Each		2	
	Total Sluice ...	...	..	...	...
	Waste weir.				
1	Earthwork excavation	C.yd.		75	
2	Surki concrete	C.ft.		249	
3	Burnt brick in surki mortar	,,		543	
4	Burnt stone slabs 4" to 6"	Sq ft.		304	
5	Plastering with surki mortar	Sqr.		5·42	
6	Rough stone work new	C.yd.		71	
	Total Weir ...	...	...	...	...
	Total of Bund, Sluice and Weir ...	...	...	...	..
	Contingencies ...	..	...	...	...
	Grand Total Rupees ...	..	...	...	...

N. LAKSHMINARSIMIAH,
Executive Engineer.

GOVERNMENT OF MYSORE ELECTRICAL DEPARTMENT.

Abstract Notification.

Attention of the public is hereby invited to the detailed Notification, dated 27th September 1930, calling for tenders for constructing electrical buildings at Chikballapur Town and for constructing a block of two Operators' quarters at Dodballapur, published in Part VI, pages 1224 to 1225 of the *Mysore Gazette*, dated 9th October 1930. The latest date for receiving tenders is 2 P.M., on 31st October 1930.

Abstract Notification.

Attention of the public is hereby invited to the detailed Notification, dated 19th September 1930, calling for tenders for constructing a Block of Operators' Quarters with a unit of latrine at Tumkur Town, published in Part VI, pages 1223 to 1224 of the *Mysore Gazette*, dated 9th October 1930. The least date for receiving tenders is 2 P.M., on the 27th October 1930.

C. M. CARIAPA,
Chief Electrical Engineer.